BRIXEN LLC

Ref.:	BRX/QT/KRIS/0909/2026	**Date:**	09 September 2026
To:	Eng. Kris	**Project:**	As per Attached Sketches
Subject:	Quotation for Aluminum Doors, Windows & Glazing Works	**Currency:**	Saudi Riyal (SAR)
Basis: Dimensions and technical requirements shown on the attached two-page sketch.		**Pricing:** Supply, fabrication, delivery and installation.	

Dear Eng. Kris,

With reference to the attached sketches, BRIXEN LLC is pleased to submit the following commercial quotation for the aluminum and glazing works. The quoted rates are based on the overall dimensions stated in the sketches and include the required aluminum framing, glass, standard hardware/accessories, fabrication, delivery and installation.

A) TECHNICAL BASIS

Finish	RAL 9005 (Jet Black).
Glazing	24 mm DGU: 6 mm Low-E tempered glass + 12 mm air space + 6 mm clear float tempered glass.
Item 1 System	Hinge Series 10 cm, Double Action Turn & Tilt, with fixed top panel.
Items 2-4 System	Royal SLD Series 12 cm, sliding/fixed configurations as indicated in the attached sketches.
Measurement Basis	Areas are calculated from the stated overall width x height. Final fabrication is subject to verified site dimensions and approved details.

B) PRICE SCHEDULE

Item	Description / Dimensions	Qty.	Unit	Unit Rate / SAR	Amount / SAR
1	Turn & Tilt window with fixed top panel; Hinge Series 10 cm; double action; RAL 9005; 24 mm DGU. Size: 0.970 x 2.770 m.	3.07	m²	1,073.84	3,296.69
2	Two-panel sliding glazed system; Royal SLD Series 12 cm; RAL 9005; 24 mm DGU. Size: 2.400 x 2.380 m.	6.2	m²	913.10	5,661.22
3	Six-panel sliding/fixed glazed system (4 fixed + 2 central sliding); Royal SLD Series 12 cm; RAL 9005; 24 mm DGU. Size: 9.564 x 2.038 m.	20.66	m²	1,141.45	23,582.36
4	Sliding glazed system with fixed top and bottom panels; Royal SLD Series 12 cm; RAL 9005; 24 mm DGU. Size: 2.641 x 3.318 m.	9.36	m²	796.98	7,459.73

Total Price (Excluding VAT)	**SAR 40,000.00**
Value Added Tax (VAT) - 15%	SAR 6,000.00
Grand Total Including VAT	**SAR 46,000.00**

C) COMMERCIAL TERMS

- **Manufacturing Period: 20 calendar days for delivery – 10 calendar days for installation .**
- **Payment Terms: 50% upon signing the contract; 45% when the materials are ready at the factory and prior to delivery, 5%After HO .**
- **IBAN: SA4080000510608010602103 – AL-Rajhi Bank**

Thank you for the opportunity to submit our offer. We look forward to working with you.
Best Regards,
BRIXEN LLC

BRIXEN LLC
C.R. 7054850701
شركة بريكسن ذ.م.م